

Statnett's R&D Conference 2019

Statnett



Innovative Technology Session

Introduction to Innovative Technology	Oddgeir Kaspersen	Statnett
Can we use aluminum for our towers?	Andreas Istad Lem	Statnett
Can we build 420 kV tower in composite?	Ivar Brovold	Statnett
Can robots help improve safety?	Livia M. Dickie	Statnett
Is digital substation a way towards next transition?	Rannveig Løken, Nargis Hurzuk	Statnett
Can we get rid of our icing problems?	Øyvind Welgaard	Statnett




Statnett R&D Conference 2019

Oddgeir Kaspersen Oslo, 02.04.2019

Statnett







Goal?

Develop technology, methods and know-how that yield

20 % increased safety

20 % faster construction time

20 % cost reduction

for construction of overhead lines, cables and substations







Statnett Innovativ Teknologi Innovative Technology

Any challenges?












What has been done?




































The future is electric



Enjoy!













Can we use aluminium for our transmission towers?






Why light-weight towers?

- HSE
- Less use of helicopter
- Life cycle emissions

Carbon footprint of two towers - comparison








Can we use aluminium towers?

- But at what price?
 - Material cost
 - Manufacturing
 - Tower erection
 - Maintenance





Bugatti la voiture noir



A few words about aluminium

- Pros:
 - Light (1/3x)
 - Strong
 - Non-corroding
 - Easy to shape
 - Recyclable

- Cons:
 - Expensive (3x)
 - Low stiffness (1/3x)
 - Poor weldability
 - VIV







Material cost

- Raw material price (3x)
- Weight efficient design
- Smart beam profiles
- Large scale production






The future is electric Prospect Steel 5 Oslo, 02.04.2019



Manufacturing

- Smart use of welding
- Simple cutting and drilling operations
- Few members
- Automation









Tower erection


- Lower weight
- Module design
- Good handling
- Docking?



Maintenance

- No corrosion
- Design to avoid vibrations
- Easy to replace parts
- Easy to climb





The future is electric Oslo, 02.04.2019



Conclusions so far



Full scale tower test

- Sucessful!
- Proof of design







Price still uncertain

- Sourcing underway
- Immature market
- Chicken or the egg






What now?

Pilot tower

- Kobbvatnet 67.5° nord
- Moderate loads
- Monitoring



Future projects

- If the cost is right
- Haugalandet (~100)
- Aurland-Sogndal (~30)

•







Aluminium towers in Norway today







The future is electric Location, date



Thank you for your attention!





Statnett R&D Conference 2019





Tower erection in Norway

- Erection with helicopter
 - Capacity 1000–1100 kg
 - 15-20 trips to erect one tower
- Standard lattice steel tower designed for helicopter erection



Why composite

- High strength to weight ratio
- Non-corrosive
- Less maintenance
- Visual impact
 - Few elements
 - "Simple/plain" design
- Fewer helicopter lifts will improve safety for workers (4-5 trips?)






History

- Re-Turn
 - 2013-2015
 - Only design not connected to production process
 - Different materials
 - Carbon fibre
 - Glass fibre
 - Epoxy
 - Design / weight / price!

Komplett mast fra NOK 665-860K serieprodusert



PRESENTASJON FASE 2A - 03.12.2014














History


- CSUB 2016-2018 Consortium: CSUB/Flowtite/Fibre Content/Amiblu
 - Continuous filament winding process glass fibre and polyester
 - Legs for externally guyed tower (limited use)






History

- Test setup
 - Wind load simulated by the weight of the pipe
 - Hydraulic cylinder with a capacity of 1200 kN
 - · Simply supported with a spherical bearing at each end









Current design

• CSUB

- Same production method for tubes (continuous filament winding)
- 4 legs internally guyed
- Tubes of glass fibre and polyester ø380 t=5.2 mm
- Sandwich cross-arm (hand lay-up)
- Glued connections
- 28 meter height
- Weight approx. 4700 kg (without insulator strings)
- Price...





Material testing


- Performed by DNV-GL Arnhem
 - Thermal linear expansion
 - Water ingress
 - Breakdown voltage
 - Dielectric test
 - Aging test
 - Tracking and erosion test
 - Fire resistance test
- No pass or fail test
 - Important information about the material
 - Semi conductive, grounding important






Electrical distances test


- Full scale test
- EGU Czech Republic







Electrical aspects - earthing





Current status

- Tender for optimization and production of prototype
- Contacted national trade organizations for composite
- Arranged meetings at JEC
- Waiting for offer



Schedule

- April: Tendering process
- Mai Oct: Design phase
- Nov 2019 Feb 2020: Production phase
- Mar Apr: Mechanical and electrical testing






Can we build 420kV towers in composite?

- Yes ©, but:
 - Cross-arm / joints (glued/bolted)
 - Fire resistance
 - Electrical challenges
 - Light tower
 - Installation time
 - Price



Thank you for your attention!





Statnett R&D Conference, Livia Dickie





Why?

- Updated regulations
- Operation & maintenance department request:
 - Robot
 - Hangs under helicopter
 - Robust and reliable
 - No more complicated than necessary










The future is electric


How?

- New lighter AWMs
- AWM clamp design
- R&D project
- EU Best Paths project
- Robot design and supply





Dalekovod






Boris Adum Statnett



What?

- No control cable
- Installation is automated
- 1 min





When?



- 2015:
 - Specification & KPIs
- 2016:
 - R&D project started
 - Prototype robot designed, built and tested
 - Prototype AWMs
- 2017:
 - 3 robots built
 - Robot compatible AWMs supplied
 - 58 AWMs installed











2018 - Ready!





Who???

- Own?
- Use?
- Statnett personnel?
- A selected contractor?
- All contractors?
- Contractor: Product versus Method








KPI 1. HSE

"Reduced amount of work at height"









KPI 2. Faster

"Better than 1 day for 1 span (6-10 AWMs)"









KPI 3. Cost

"At least 20% less"

- 2018: 282 AWMs installed with robot
- Lowest average price "per AWM"
- Risk versus Reward





More robots?



- De-installation robot?
- Spacer robot?
- What else could the AWM robot install?



Can robots help improve safety?





R &D Conference


Rannveig Løken and Nargis Hurzuk Oslo, 2 April 2019





What is digital substation?

- IEC 61850
- Station bus
- Process bus



Is digital substation a way towards next transition?


- Smaller
- Smarter
- Safer





Smaller- reduced footprint

- Substation Layout
- Cable trenches
- Control room
- IED





Smarter- datacollection

- Added functionality
- Adaptable to future needs
- Asset management
- Flexibility



The future is electric 5



Safer- New architecture


- LPIT
- Processbus
- Remote access
- Cyber security





Bay Cabinet- New design

- EMP protection
- Climatic condition
- Optimal Maintenance
- Cyber security





Testing and network analysing

- DANEO
- System verification
- Best Master Clock





Project outcome

- Interoperability
- Cooperation
- Competance
- System design





Is digital substation a way towards next transition?

- Smart
- Secure
- Effective



The future is electric 10




Statnett R&D Conference 2019





Icing in Norway

- Topography ideal for power line icing
 - High mountains
 - Windy
 - Fjords
- Unofficial world record of 305 kg/m at Lønnahorgi in 1961






Icing in Statnett

- Cause for approx. one collapse per year last decade
 - One event cost over 20 MNOK in NDE only
- Many power lines in exposed areas







FRonTLines

- 2015-2018
- Focus on modelling of ice-loads
- Established 3 measuring stations still in operation
- Improved ice accretion and shedding model
- NRC funded project







- 2018 2021
- Total budget: 36 MNOK



• 2 PhD














LANDSNET





- WP1 Sensors and measuring stations
 - Smart and energy-effective ice-load-sensors
 - Environmentally firendly power supply
 - Batteries
 - Fuel-cell








- WP2 Monitoring
 - Live monitoring
 - Current ice load
 - Web cam images
 - Icing forecast
 - 72 hours
 - Weather window for ice removal










- WP3 Modeling and climate change
 - Improve models
 - Ice accretion
 - Shedding
 - Models for icing map
 - Climate change







- WP4 Ice map
 - Icing map for all of Norway
 - Climate change
 - Different return periods
 - Orientation of power line
 - GIS
 - Mapping of existing lines







- WP5 Ice prevention
 - Workshop Oct 2018
 - Theoretical demonstration
 - Coating
 - OPPC
 - Induction spirals
 - Wet snow rings
 - Removal of shield wire
 - Combination of methods








- WP6 Ice removal
 - Evaluate and improve existing methods
 - Timber pole
 - Increased current
 - Investigate other methods
 - Drones
 - Robots







The future is electric



Can we get rid of our icing problems?

- Maybe not ⊗, but:
 - We can reduce them significantly © by:
 - Choosing smarter routes
 - Implement ice prevention technologies
 - Monitoring high risk areas
 - Developing ice removal methods for all conditions









Thank you for your attention ©

